

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

DIVISION: BYATARAYANAPURA

SUB DIVISION: VIDYARANYAAPURA

Name of Work: Modified Estimate for Improvements to Roads and Drains at Chikkavenkatappa Layout, Deshbandunagara and Surrounding area in Ward No. 13, (Doddabommasandra).

Job Code: 013-23-000012

Estimated Cost: Rs. 55.00 Lakhs

Approved Cost: Rs. 45.37 Lakhs

Modified Cost: Rs. 45.36 Lakhs

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

NOTE OF WORK:- Modified Estimate for Improvements to Roads and Drains at Chikkavenkatappa Layout, Deshbandunagara and Surrounding area in Ward No. 13, (Doddabommasandra).

Estimation Cost Rs. 4536199.00

SI No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
1	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge Item No. 19.2.1, Page No. 163, Vol - II PWD SR 2021-22	Cum									
			Not Executed								
									0.00	1364.12	0.00
2	Providing, laying and spreading available soil in the embankment on a prepared surface, pulverising, mixing the spreaded soil in place with Soil stabilisor with 2% of slaked lime using Binder spreader Machine having minimum content of 70% of CaO, grading with the motor grader and compacting with the road roller at OMC to the desired density to form a layer of improved embankment. (By Mechanical Means, Item no. 4.11, Page No. 21, Vol - III PWD SR 2021-22	Cum									
	For Road Work										
	5th Main Road Deshabandunagara From Cross Road		1	15.00	4.40	4.60	4.50	0.45	30.38		
			1	15.00	4.60	4.35	4.48	0.45	30.21		
			1	15.00	4.35	4.30	4.33	0.45	29.19		
			1	15.00	4.30	4.10	4.20	0.45	28.35		
			1	15.00	4.10	4.10	4.10	0.45	27.68		
			1	15.00	4.10	3.90	4.00	0.45	27.00		
			1	15.00	3.90	4.00	3.95	0.45	26.66		
			1	14.00	4.00	4.20	4.10	0.45	25.83		
									225.29	722.75	162830.00
3	Earth work Excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. (PWD SR 2021-22 Vol -I Pg No 5 item no 1.4.1)	Cum									

Sl No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
	New Drain										
	5th Main Road Deshabandunagara E/S		1	130.50			1.00	1.00	130.50		
	5th Main Road Deshabandunagara W/S		1	55.40			1.00	1.20	66.48		
	Chikkavenkatappa Layout		1	40.00			1.50	1.20	72.00		
	Culvert										
			1	5.50			1.40	1.00	7.70		
	Desilting of Drain										
			1	136.50			0.60	0.60	49.14		
			1	38.00			0.90	0.60	20.52		
	For Road Work										
	5th Main Road Deshabandunagara From Cross Road		1	15.00	4.40	4.60	4.50	0.20	13.50		
			1	15.00	4.60	4.35	4.48	0.20	13.43		
			1	15.00	4.35	4.30	4.33	0.20	12.98		
			1	15.00	4.30	4.10	4.20	0.20	12.60		
			1	15.00	4.10	4.10	4.10	0.20	12.30		
			1	15.00	4.10	3.90	4.00	0.20	12.00		
			1	15.00	3.90	4.00	3.95	0.20	11.85		
			1	14.00	4.00	4.20	4.10	0.20	11.48		
	For Rain Water Pit										
	Chikkavenkatappa Layout		2	3.142x1.5x1.5				3.30	11.66		
				4							
	Total								458.13	199.16	91242.00
4	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (PWD SR 2021-22 Vol -I Pg 15 item no 2.1.3)	Cum									
	New Drain										
	Bed Concrete										
	5th Main Road Deshabandunagara E/S		1	130.50			1.00	0.15	19.58		
	5th Main Road Deshabandunagara W/S		1	55.40			1.00	0.15	8.31		
	Chikkavenkatappa Layout		1	40.00			1.50	0.15	9.00		
	Culvert										
			1	5.50			1.40	0.15	1.16		
	Bed Concrete										
	Rising of Drain bed Concrete		1	136.50			0.60	0.30	24.57		
	Bed Concrete		1	38.00			0.90	0.15	5.13		
	Total Qty								67.74		
	Qty upto 125%								60.00	5946.89	356813.00

SI No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
	Qty Above 125%								7.74	5946.89	46029.00
	Issued Rate 07-07-2022 Basic rate	5554.00									
	Area weightage 10%	555.40									
	Sub Total	6109.40									
	Tender Premium -2.66%	-162.51									
	Grant Total	5946.89									
5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately) (PWD SR 2021-22 Vol -I Pg 17 item no 2.4.2))	Cum									
	New Drain										
	Raft										
	5th Main Road Deshabandunagara E/S	1	130.50				0.90	0.15	17.62		
	5th Main Road Deshabandunagara W/S	1	55.40				0.90	0.15	7.48		
	Chikkavenkatappa Layout	1	40.00				1.20	0.15	7.20		
	Culvert										
		1	5.50				1.30	0.20	1.43		
	Side Wall										
	5th Main Road Deshabandunagara E/S	2	130.50				0.15	0.60	23.49		
	5th Main Road Deshabandunagara W/S	2	55.40				0.15	0.90	14.96		
	Chikkavenkatappa Layout	2	40.00				0.15	0.90	10.80		
	Culvert										
		2	5.50				0.30	0.65	2.15		
	Total								85.12	6709.69	571125.00
6	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. MORTH Specification NO.1600&2200 (PWD SR 2021-22 Vol - III Pg 99 item no 13.1)	tonne									

Sl No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
	For Drain	Cum							85.12		
		kg							0.075		
		tonne							6.38		
	Total								6.38	98690.11	630034.00
7	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. (Approved Data Rate)	Sqm									
	Covering Slab										
	5th Main Road Deshabandunagara E/S		1	122.00			0.90		109.80		
	5th Main Road Deshabandunagara W/S		1	55.40			0.90		49.86		
	Damaged Slabs of Item No. E1		1	53.00			0.90		47.70		
	Chikkavenkatappa Layout		1	40.00			1.20		48.00		
			1	38.00			1.20		45.60		
	Rain water pits		2		3.142x1.2x1.2				2.26		
					4						
	Total								303.22	2016.88	611563.00
8	Construction of Dry Lean Cement Concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ m3 , optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing. MORTH Specification No. 601 (PWD SR 2021-22 Vol - III P.No. 43 - I.No. 6.1)	Cum									
	CC Road										
	5th Main Road Deshabandunagara From Cross Road		1	15.00	4.40	4.60	4.50	0.15	10.13		
			1	15.00	4.60	4.35	4.48	0.15	10.07		
			1	15.00	4.35	4.30	4.33	0.15	9.73		
			1	15.00	4.30	4.10	4.20	0.15	9.45		
			1	15.00	4.10	4.10	4.10	0.15	9.23		
			1	15.00	4.10	3.90	4.00	0.15	9.00		
			1	15.00	3.90	4.00	3.95	0.15	8.89		
			1	14.00	4.00	4.20	4.10	0.15	8.61		
	Total								75.10	4309.73	323650.00

Sl No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
	Providing and constructing un-reinforced plain Cement Concrete Pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, primer, sealant, curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete MORTH Specification No.1501 . as per the directions of the Engineer-in-charge of the work. (PWD SR 2021-22)	Cum									
	CC Road										
	5th Main Road Deshabandunagara From Cross Road		1	15.00	4.40	4.60	4.50	0.15	10.13		
			1	15.00	4.60	4.35	4.48	0.15	10.07		
			1	15.00	4.35	4.30	4.33	0.15	9.73		
			1	15.00	4.30	4.10	4.20	0.15	9.45		
			1	15.00	4.10	4.10	4.10	0.15	9.23		
			1	15.00	4.10	3.90	4.00	0.15	9.00		
			1	15.00	3.90	4.00	3.95	0.15	8.89		
			1	14.00	4.00	4.20	4.10	0.15	8.61		
	Total								75.10	6972.66	523629.00
10	Loading and Unloading of Stone Boulder / Stone aggregates / Sand / Kankar / Moorum. (Tipper 14 m3) (PWD SR 2021-22 Vol-III Page No.3, Item No.1.1C)	Cum									
	Qty Vide of Item No- (3)								458.13		
	Total								458.13	79.23	36298.00
	Basic rate	74.00									
	Area Weightage 10%	7.40									
	Total	81.40									
11	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km (PWD SR 2021-22 Vol-III Page No. 3, Item No.1.4B)	T.Km									
	Qty vide Item No - 10			458.13			1.28		586.41		

Sl No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
	Total								586.41	112.43	65930.00
	15Km 7*15	105.00									
	Area Weightage 10%	10.50									
	Total	115.50									
	BOREWELL										
12	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1)Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a)Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed	Each BW									
			1						1	5004.25	5004.00
13	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete (P. 151 / I. 1) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Rmtr									
	0 to 50 m		1	50.00					50.00	282.29	14115.00
14	50 to 100 m		1	50.00					50.00	354.32	17716.00
15	100 to 150 m		1	50.00					50.00	376.71	18836.00
16	150 to 200 m		1	50.00					50.00	437.00	21850.00
17	200 to 250 m		1	50.00					50.00	512.98	25649.00
18	250 to 300 m		1	50.00					50.00	543.16	27158.00
19	300 to 350 m										
			Not Executed								

SI No	Description of work	Unit	Measurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
20	Supply of ISI mark 175mm nominal bore, plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest amendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m. prices include Collar - Medium duty (P. 154, I. 32) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Rmtr									
			1	60.00					60.00	1881.58	112895.00
21	Providing 250mm dia PVC Pipe 6kg/cm (P. 34, I. 1175) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Rmtr									
			1	18.00					18.00	1070.74	19273.00
22	Providing and fixing Borewell Cap & Clamp Set P. XLVII, SI No. 17 PWD SR 2018-19	Set									
			1						1	1752.12	1752.00
23	Providing, supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and conforming to IS 8034-2000; 3Phase, SS Bowl & Impeller with Low volt Motor as per specifications, as per necessary amendments and instructions of engineer incharge of work 12.50 HP - 90 LPM @ 264 m = 24 STG Outlet Dia - 2.00 (P. 161, I No. 17.7) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	No									
			1						1	61808.95	61809.00

Sl No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
24	Providing, Laying and Fixing GI pipes conforming to IS 1239:1990 with latest amendments complete with GI fittings (excluding the cost of fittings) with cuts and threads wherever necessary, including testing for water tightness, with all lead and commissioning. (contractor will make his own arrangements for procuring water for testing) Medium Duty GI pipe of 50mm dia (P 142, I No. 2.6), WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	m									
			1	250.00					250.00	466.26	116565.00
25	Providing wrought mild steel (galvanized) 50 mm dia GI collar confirming to IS 1239-II, 1991 with latest amendments if any. (P. 144, I No. 6.5) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Nos									
			1	42					42	213.17	8953.00
26	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments 50 mm (P. 162, I No. 28.1) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Nos									
			1						1	1241.00	1241.00
27	Supply and delivery at site brand new best make starter/ control panel suitable for following HP centrifugal pump confirming with ISI mark and its latest amendments 10 to 120 HP centrifugal pump (P. 165, I No. 49.3) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	No.									
			1						1	34536.23	34536.00
28	Submersible Cable 1x3x6.0 Sq.mm (PWD SR 2018-19 Page No. XLVII SI No. 8)	M									
			2x1	280.00					560	140.17	78495.00
29	Labour charges for Erection of new / repaired submersible pump set along with GI pipes (32mm / 50mm), cable (New submersible pump set if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (Each length = 6 m) (P. 154, I No. 28) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Job									

Sl No	Description of work	Unit	Measurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
			1	42					42	146.98	6173.00
30	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws., P No. 24 / I No. 5.6.6 KPWD Electrical SR 2019-20	Each									
			1						1	284.23	284.00
31	Providing, Supplying and fixing suitable for 1.1 KV class UG cable filled with necessary bitumen / insulating compound complete with terminals, clamps, bolts, nuts and washers etc. with necessary materials and labour tools and equipments as per instructions of engineer incharge of work. 3½x6 Sqm (P. 164, I No. 44.1) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Mtr									
			1	30.00					30.00	501.30	15039.00
32	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. (As per Civil SR KSRB I-2, P-7) P No. 41 / I. No. 6.6.1 KPWD Electrical SR 2019-20	Mtr									
	For Cutting Road Surface		1	30.00					30.00	73.98	2219.00
33	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV. P. No. 41 / I No. 6.9.1 KPWD Electrical SR 2019-20	Mtr									
	40mm dia GI pipe		1	4.00					4.00	326.09	1304.00
34	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc. P. No. 42 / I.No. 7.10.2 KPWD Electrical SR 2019-20	No.									
	16Sqmm		1						1.00	262.82	263.00

Sl No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
35	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia (P. 164, I No. 45) WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Job	1						1	3650.25	3650.00
36	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. P No. 24 / I No. 5.7.2 KPWD Electrical SR 2019-20	No.	1x6						6	169.37	1016.00
37	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 6-32Amps TPN P No. 27 / I No.5.17.7 KPWD SR 2019-20	No	1						1	1669.38	1669.00
38	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete P.No. 30, I. No. 5.42.2 KPWD Electrical SR 2019-20	Sq.Cm	2x1	120.00			60.00		14400.00		
	16SWG		1	360.00			25.00		9000.00		
									23400.00	0.34	7956.00


Sl No	Description of work	Unit	Measurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
39	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means above 600 mm trench width as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & boning rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required, utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m (P. 10, I 1.17.1) PWD SR 2021-22 Vol. I	Cum									
			1	90.00			0.45	0.60	24.30		
									24.30	207.72	5048.00
40	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately MORTH Specification No. 202 (PWD SR 2021-22 Vol -III P.No.10 - I.No.2.19)	Cum									
	CC Road										
	Pipeline		1	60.00			0.45	0.25	6.75		
									6.75	451.85	3050.00
41	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete., 75mm(weight of pipe -0.917 kg P .139, I No. 13.1 WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Rmtr									
	75 mm dia 6 KSC PVC pipe		1	150.00					150.00		
									150.00	204.41	30662.00


SI No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
42	Refilling available earth around trenches / pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications Item No. 1.10 Page No. 7, PWD SR 2021-22 Vol-I	Cum									
			Qty. Vide Item No. 39						24.30	100.26	2436.00
43	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendment Size 65 mm P .162, I No. 27.2, WATER SUPPLY AND UGD WORKS COMMON SCHEDULE OF RATES 2021-22 Volume - V	Each									
			5						5	1508.77	7544.00
	EIRL										
E1	Removing and resetting of footpath slab (Approved arrival rate)	Sqm									
	Drain Covering Slab										
			1	136.50				0.90	122.85		
	Consider 60% of Total Qty								71.25		
	Basic rate	235.00									
	Tender Premium -2.66%	-6.25									
	Grant Total	228.75									
									71.25	228.75	16299.00
E2	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) Item No. 5.4, Page No. 9, Vol - II PWD SR 2021-22	Cum									
	SSM Wall										
			2	38.00			0.45	0.50	17.10		
	Basic rate	5422.00									
	Area weightage 10%	542.20									
	Sub Total	5964.20									
	Tender Premium -2.66%	-158.65									
	Grant Total	5805.55									
	Total								17.10	5805.55	99275.00

Sl No	Description of work	Unit	Measurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
E3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate (PWD SR 2021-22 Vol -I Pg 15 item no 2.1.4))	Cum									
	Drain Vent Conrete										
			1	136.50			0.60	0.20	16.38		
			1	38.00			0.90	0.15	5.13		
	Flagging Course										
			2	136.50			0.15	0.10	4.10		
			2	38.00			0.45	0.15	5.13		
	Issued Rate 07-07-2022 Basic rate	5728.00									
	Area weightage 10%	572.80									
	Sub Total	6300.80									
	Tender Premium -2.66%	-167.60									
	Grant Total	6133.20									
									30.74	6133.20	188504.00
E4	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications PWD SR 2021-22, Page No. 17, Item No. 6.33, Vol - II	Sqm									
	Flagging Course										
			2	136.50			0.20		54.60		
	Basic Rate	1067.00									
	Area Weightage @ 10%	106.70									
	Total	1173.70									
	Tender Premium -2.66%	-31.22									
	Grant Total	1142.48									
									54.60	1142.48	62379.00

Sl No	Description of work	Unit	Mesurement						Qty.	Rate	Amount
			No.	L	B1	B2	Av.B	D			
E5	Providing and Fixing pre cast Covering Slab 230 mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge	Sqm									
	For Culvert										
			1	5.50			1.20		6.60		
	Data rate	5037.00									
	Tender Premium -2.66%	-133.98									
	Grant Total	4903.02									
									6.60	4903.02	32360.00
E6	RCC NP 4 1200mm dia SI No. 53, P No. A-40, PWD SR 2021-22 Vol - I	Mtrs									
	For Pipe										
			2	3.30					6.60		
	Data rate	9555.00									
	Tender Premium -2.66%	-254.16									
	Grant Total	9300.84									
									6.60	9300.84	61386.00
E7	Stone Aggregate (Single size) :40 mm nominal size PWD SR 2021-22 (P. 61 / I. 2.1.1)	Cum									
	Rain Water Racharging Pits		2	3.142x1.2x1.2			1.00		2.26	1190.48	2693.00
				4							
Grand Total										4536199.00	


Rupees Forty Five Lakh(s) Thirty Six Thousand One Hundred Ninety Nine Only


Assistant Engineer
Ward No. 13, Doddabommasandra


Assistant Executive Engineer
Vidyaranyapura Sub Division
Vidyaranyapura Sub Division
B.B.M.P, Bangalore - 97


Executive Engineer
Byadarayanapura Division
ಬೃ.ಪಿ.ಮ.ಪಾ, ಬೆಂಗಳೂರು

Technical Sanction
Accorded For Rs. 4536199.00
Head of A/C. P. 2726
CER NO : 03 Dt. 24/04/23



C.E.